

DIGI-CRAC™

FACILITY:
DATA CENTER
BEIJING, CHINA



Building Information



» Function: Data center

System Information

- » Space condition requirements are 18-26° C for temperature
- » 45%-65% relative humidity
- » Current setpoints are 20-22° C
- » Current setpoints are 45% relative humidity
- » Three (3) 25-ton DX units with two compressors

Project Date

» Implementation January, 2013



DIGI-CRAC™

- » M&V for baseline mode 2 week period
- » M&V for energy efficiency mode 2 week period
- » Improve existing hot/cold spot situation and enhance temperature and relative humidity control to satisfy equipment operating condition.
- » Install return air registers and return air duct work for Lab Room #3
- » The air conditioning system can operate at optimal efficiency.
- » Improve the HVAC system reliability and stability.
- » Reduce maintenance cost, and prolong equipment life.
- » Through duct work modification for Lab Room #3 eliminate equipment overheat that has caused system alarms.

BENEFITS

- » Improved system reliability
- » Standard electricity usage: 50.38 kWh/hr
- » Electricity usage with Digi-CRAC: 36.07 kWh/hr
- » Energy savings:
 - » Electricity: CRAC 1 **(38.3%)**
CRAC 2 **(39.7%)**
- » Project simple payback: **1.8-2.1 years**

*A third CRAC unit generated 9.74% energy reduction, however it is removed from this case study because of its abnormal operating and cooling requirements.